


New Hampshire Optical Systems
 New Hampshire Optical Systems, Inc.
 99 Pine Hill Rd.
 Nashua, NH 03063
 (603-821-6467)

**Proposed
 Railroad Crossing
 Whitefield, NH**



Project # TID-128 - Primary 6
 Drawing # AC-WHI-RR-2

Date: 04/25/13
 Revision # 1

**Proposed
 Railroad Crossing
 Whitefield, NH**

Location:
 Lancaster Rd, Whitefield NH
 Nearest cross street- Jefferson Rd.



LOCUS MAP
(Not to Scale)



Spanmaster® Release 3.1 Sag / Tension Computations
09/01/11 Waveguide

Waveguide
River and Rail Crossings


| Selected Cables | X-SECT AREA (sq.in) | EFF MODULUS (psi) | NOMINAL DIAM (in) | EFF.EXP. COEFF. (1/F) | CABLE WEIGHT (lb/ft) | E*A LOAD BEARING CAPACITY (lbs) | MAX. RATED LOAD (lbs) |
|---------------------|---------------------|-------------------|-------------------|-----------------------|----------------------|---------------------------------|-----------------------|
| 1/4"6.6mEHS | 0.0352 | 2.60E+07 | 0.250 | 5.60E-06 | 0.1210 | 914940 | 6650 |
| ORF-O-144-LN Bundle | 0.4307 | 3.50E+05 | 0.741 | 1.09E-05 | 0.1520 | 150720 | 640 |
| | | | 0.991 | | 0.2730 | | |

NESC RESULTS

| Loading Condition | Temp. (F) | Ice Load lb/ft | Ice Thick in | Wind Constant lb/ft | Horz Wind Load lb/sq ft | Result Load + Const lb/ft | Sag ft | Tension lb | % Len Chg From Input Conditions | Sag @ Point 60.5 ft | Horz Sag Comp ft | Vert Sag Comp ft | Vector Angle Deg |
|------------------------|-----------|----------------|--------------|---------------------|-------------------------|---------------------------|--------|------------|---------------------------------|---------------------|------------------|------------------|------------------|
| Rule 251 - Heavy 232A1 | 0.0 | 0.927 | .50 | .3 | 4.0 | 1.671 | 2.24 | 1363 | 0.06 | 2.24 | 1.08 | 1.96 | 28.9 |
| | 120.0 | 0.000 | .00 | .0 | 0.0 | 0.273 | 1.56 | 320 | 0.02 | 1.56 | 0.00 | 1.56 | 0.0 |

| Temp (F) | Midspan Sag (ft) | Tension (lb) | % Length Change | Clearance |
|----------|------------------|--------------|-----------------|-----------|
| -40.0 | .63 | 797 | -0.02 | N/A |
| -30.0 | .66 | 754 | -0.02 | N/A |
| -20.0 | .70 | 711 | -0.02 | N/A |
| -10.0 | .74 | 671 | -0.02 | N/A |
| .0 | .79 | 631 | -0.02 | N/A |
| 10.0 | .84 | 594 | -0.01 | N/A |
| 20.0 | .89 | 558 | -0.01 | N/A |
| 30.0 | .95 | 525 | -0.01 | N/A |
| 40.0 | 1.01 | 493 | -0.01 | N/A |
| 50.0 | 1.08 | 464 | -0.01 | N/A |
| 60.0 | 1.14 | 437 | 0.00 | N/A |
| 70.0 | 1.21 | 413 | 0.00 | N/A |
| 80.0 | 1.28 | 390 | 0.00 | N/A |
| 90.0 | 1.35 | 370 | 0.01 | N/A |
| 100.0 | 1.42 | 352 | 0.01 | N/A |
| 110.0 | 1.49 | 335 | 0.01 | N/A |
| 120.0 | 1.56 | 320 | 0.02 | N/A |
| 130.0 | 1.63 | 306 | 0.02 | N/A |
| 140.0 | 1.70 | 294 | 0.03 | N/A |

Span Length = 121.00 ft
Span Sag = 1.21 ft (14.5 in)
Span Tension = 413 lb
Max Load = 6,650 lb
Usable load (60%) = 3,990 lb
Catenary Length = 121.032 ft
Stress Free Length @ Installed Temperature = 120.978 ft
Unloaded Strand Sag = .80 ft (9.6 in) 0.66 %
Tension = 276 lb



E-42/14 - T-1/5
(Existing joint owned utility pole (PSNH/Fairpoint) in existing Right-of-Way)

E-42/15 - T-1/4.5
(Existing joint owned utility pole (PSNH/Fairpoint) in existing Right-of-Way)



E-42/14 - T-1/5

Construction Notes:

NHOS proposes to install a 1/4 inch metal supporting strand between the existing utility poles shown above that will traverse the railroad. The strand will be installed at the proposed height (see above). The supporting strand will be secured to each pole using double dead end attachments to prevent any sag in the wire and maintain proper clearances. NHOS will lash a one inch diameter fiber optic cable (PVC jacket) to the strand using a dual lash method to provide security of the fiber over the right of way. The fiber will be tagged with twenty four hour contact information at each pole clamp. NHOS will employ the proper safety personnel during the crossing installation. The proposed install will meet all proper clearances from other Utilities. (see above). Additional pole guys will be added per NESC Rule 264 and as directed by pole owners.



E-42/15 - T-1/4.5



New Hampshire Optical Systems, Inc.
99 Pine Hill Rd.
Nashua, NH 03063
(603-821-6467)

Proposed Railroad Crossing Whitefield, NH

Notes:

- The heights of structures shown hereon are based on field measurements taken with a Nikon 362 total station during a site survey on 10/12/11.
- Vertical distances are representative of attachment heights after utility make ready moves are completed.

Project # TID-128 - Primary 6
Drawing # AC-WHI-RR-2

Date: 04/25/13
Revision # 1

Proposed Railroad Crossing Whitefield, NH

Location:
Lancaster Rd, Whitefield NH
Nearest cross street- Jefferson Rd.