



EXHIBIT B

Manholes in State House steam piping loop

<u>Location</u>			Sidewalk	W	L	H	CY
1	Park St	State House loop	X	6	6	4	5.33
2	Park/Green	State House loop	X	6	6	4	5.33
3	School/Green East	State House loop	X	4	4	4	2.37
4	School/Evans In	State House loop	X	4	4	4	2.37
5	Capitol St	State House loop	X	4	6	4	3.56
Valve box	School St	State House loop	X	2	2	2	0.30

All valves in manholes to be closed

Manholes to be filled with dig able flowable fill

Connecting trap piping to be cut and capped in manhole

Manhole ring must be removed

Top of manhole is the sidewalk and must be removed and  
new concrete poured for sidewalk